## CUSTOMER ACKNOWLEDGEMENT

Customer acknowledges that these Installation Instructions are part of the product specification, and that the attached Installation Registration Form will be provided to the installer to sign and return to Kenall after installation is complete. This signed release is required by Kenall before order will be released into production.

| Signature: | Date: |
|------------|-------|
|            |       |

Print Name: \_\_\_\_\_

Company Name:\_\_\_\_\_

## **IMPORTANT SAFEGUARDS**

To prevent MRI machine interference, all DC power and dimming signal wiring must be completely shielded within grounded aluminum conduit and a suitable MRI room EMI filter must be installed on each line.

When using electrical equipment, basic safety precautions should always be followed, including the following: THIS PRODUCT MUST BE INSTALLED IN ACCORDANCE WITH THE APPLICABLE INSTALLATION CODE BY A PERSON FAMILIAR WITH THE CONSTRUCTION AND OPERATION OF THE PRODUCT AND THE HAZARDS INVOLVED.

## **SAVE THESE INSTRUCTIONS**

- Disconnect power to all circuits before wiring system.
- Install in accordance with all national, state, and local codes.
- Do not connect to an ungrounded supply.
- Wiring connections must be made internal to the enclosure.
- Failure to install unit on a mechanically-sound surface may result in personal injury, physical damage, or potential fire hazard.
- Use installation procedures appropriate for an environment involving MRI and sensitive electronic equipment.
- Read all markings and labels to ensure correct installation of the power supply. Supplemental instructions may be located on the enclosure, in addition to this instruction sheet, regarding orientation, or mounting restrictions.
- Read instructions provided with the MedMaster<sup>™</sup> MRIPS-312 external power supply for proper installation and electrical connection to the lighting system.



## CUSTOMER ACKNOWLEDGEMENT MRI INSTALLATION REGISTRATION FORM

Customer acknowledges that the attached Installation Registration Form will be provided to the installer to sign and return to Kenall afterinstallation is complete. For warranty purposes, please fill out this form and return to Kenall by fax at (847) 360-1781.

I certify that the lighting installation for the listed MRI suite location is completed per the provided installation instructions and to the best of my abilities.

Please check off items to denote status:

- □ Installation instruction sheets for MRIPS-312 power supply and individual luminaire(s) read and followed.
- □ MRIPS-312 power supply and EMI filters are located outside the shielded enclosure.
- □ All DC supply wiring is completely enclosed within grounded aluminum conduit. Installation has no ungrounded/unshielded portions of conduit or openings of any size or shape.
- □ All dimming signal wiring is completely enclosed within grounded aluminum conduit. Installation has no ungrounded/unshielded portions of conduit or openings of any size or shape. Check here if dimming is not applicable: □
- □ MRI Room EMI filters for the 24VDC supply are of the type intended for MRI suites and are sized to the electrical load.
- □ DC supply power and dimming signal are NOT running through the same EMI filter. Check here if dimming is not applicable: □
- Lighting system fully tested (including dimming operation, if applicable) while MRI machine is in idle and scan operation mode.

If any of these steps cannot be completed or you need technical assistance, please contact Kenall Technical Support at 1-800-4KENALL (1-800-453-6255).

| Electrical Contractor     | Installation Site              |  |
|---------------------------|--------------------------------|--|
| Name:                     | Name:                          |  |
| City/State:               | City/State:                    |  |
| Phone:                    | <br>FAX FORM TO (847) 360-1781 |  |
| Installation Date:        |                                |  |
| (Do not write below line) |                                |  |
| Kenall Received By:       | Received Date:                 |  |
|                           |                                |  |
|                           |                                |  |

